

Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: September 9-11, 2008

PREPARED FOR: Cory Scott (PacifiCorp)
Linda Prendergast (PacifiCorp)

PREPARED BY: Ken Carlson (CH2M HILL)
Richard Raymond (E&S Environmental Chemistry)

DATE: September 22, 2008

Introduction

This technical memorandum summarizes the latest results of monitoring during 2008 of blue-green algae (BGA) species and the associated toxin microcystin above, below, and in the vicinity of PacifiCorp's Klamath Hydroelectric Project (Project). This monitoring is particularly focused on *Microcystis aeruginosa* (MSAE), a BGA species with a recent history of summertime blooms in Copco and Iron Gate reservoirs that is capable of producing microcystin. This monitoring also estimates the presence of other potentially-toxigenic BGA species, including *Anabaena spp.* (ANAB) and *Planktothrix (Oscillatoria) spp.* (PLKT). This monitoring is one of several water quality studies being conducted by PacifiCorp in the vicinity of the Project in 2008 in support of on-going assessment of water quality conditions and potential management actions (PacifiCorp 2008a and 2008b).

The results specifically addressed in this memorandum are for samples collected on September 9-11, 2008. Earlier results from sampling in April, May, June, July, August, and September 2008 are discussed in previous memoranda (Carlson and Raymond 2008a, 2008b, 2008c, 2008d, 2008e, 2008f). PacifiCorp plans to prepare subsequent memoranda such as this on a rolling basis to summarize the results to date of BGA species and microcystin sample analysis. PacifiCorp plans to prepare a final report of the results and interpretation of the complete set of collected data after the conclusion of the sampling effort in winter 2008-09.

Methods

Phytoplankton sampling for laboratory analysis of potentially-toxigenic BGA species, notably MSAE, and microcystin is occurring routinely at 23 sites in the vicinity of the Project listed in Table 1, including:

- Eight river sites upstream, within, and downstream of the Project area that were sampled during PacifiCorp's 2008 water quality monitoring study (as further described in PacifiCorp 2008c and 2008d).

- Two open-water reservoir sites in the lower ends of Iron Gate and Copco reservoirs (near the log booms) that are associated with PacifiCorp's 2008 water quality monitoring study (as further described in PacifiCorp 2008c and 2008d). During the sampling of September 10, a new non-routine open water site was sampled in Iron Gate reservoir inside the log boom near the forebay (as explained further below).
- Four shoreline sites in coves in Copco and Iron Gate reservoir (i.e., two cove sites in each reservoir). These are similar to sites as monitored in previous years by the Karuk Tribe.
- Four shoreline sample locations in the lower basin of Upper Klamath Lake.
- Five open-water sample locations in the vicinity of solar-powered circulators deployed in the upper end of Copco reservoir during 2008 (in conjunction with PacifiCorp's testing of circulators in Copco reservoir).

Sampling has been and will be conducted at the routine river and open-water monitoring sites once per month in April, May, November, and December, and twice per month in June through October. Samples have been and will be taken at the shoreline locations in the reservoirs once per month in April, May, October, and November and twice per month in June through September. Samples from the four shoreline locations in UKL have been and will be obtained once in June and twice per month in July through September. Samples at the sites in the vicinity of solar-powered circulators in Copco reservoir have been and will be obtained once in May and twice per month from June through October.

A total of 31 samples from 19 sites were collected during September 9-11, 2008¹. One sample was taken from each of the eight river sites as grab samples offshore in the current at approximately 0.5 meters (m) below the surface. One sample was taken from each of the four shallow reservoir shoreline sites (e.g., cove sites) and the four shoreline locations in UKL as a surface grab sample over the top 30 cm depth. As during previous sampling dates, three samples were taken from each of the two open-water sites near the log booms in Copco and Iron Gate reservoir, including: (1) a surface grab sample over the top 30 cm depth; (2) an integrated vertical sample from the surface to a depth of 8 m (approximately the depth of the reservoir's photic zone), and (3) a horizontal integrated sample (over a distance of about 150 ft) at a depth of 0.5 m below the surface.

During the sampling of September 10, nine additional non-routine samples were collected in Iron Gate reservoir to acquire data to help assess the effectiveness of the barrier curtain installed at the log boom. Four additional samples were collected at the open water site in Iron Gate reservoir at the log boom (located at the upstream side). These additional samples included grab samples at depths of 10, 20, 30, and 40 m. Also, five additional samples were collected at a new open water site in Iron Gate reservoir inside the log boom near the forebay. These additional samples included grab samples at depths of 0.3, 0.5, 10, 20, and 30 m.

¹ Note: on September 16, 2008, additional samples were taken from each of the five open-water sample locations in the vicinity of solar-powered circulators deployed in the upper end of Copco reservoir. However, results for these samples were not yet available from the analytical laboratory as of the date of this memo.

Table 1. Sites of Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring in the Vicinity of the Klamath Hydroelectric Project During 2008.

Location	Approximate River Mile	River Sites	Reservoir Open Water Sites	Reservoir Shoreline Sites	UKL Shoreline Sites	Test Circulator Monitoring Sites
Upper Klamath Lake near Eagle Ridge ramp	UKL				X	
Upper Klamath Lake near Hagelstein Park	UKL				X	
Upper Klamath Lake at Wocus Bay	UKL				X	
Upper Klamath Lake at Pelican Bay ramp	UKL				X	
Link River below Upper Klamath Lake	253.1	X				
Klamath R. below Keno dam	233.4	X				
Klamath R. below J.C. Boyle powerhouse	220.0	X				
Klamath R. above Copco reservoir	206.4	X				
Copco reservoir upper end at Copco Village (SB 1)	204.0					X
Copco reservoir upper end near "narrows" (SB 2)	203.0					X
Copco reservoir middle above Mallard Cove (SB 3)	202.0					X
Copco reservoir at Mallard Cove ramp	201.5			X		
Copco reservoir middle below Mallard Cove (SB 4)	201.0					X
Copco reservoir middle near Copco Cove (SB 5)	200.0					X
Copco reservoir at Copco Cove ramp	200.0			X		
Copco reservoir lower end at log boom	198.6		X			
Iron Gate reservoir at Camp Creek area	192.8			X		
Iron Gate reservoir at Williams boat ramp	192.4			X		
Iron Gate reservoir lower end above log boom	190.2		X			
Iron Gate reservoir lower end near forebay ²	190.1		X			
Iron Gate powerhouse tailwaters	190.1	X				
Klamath R. at Iron Gate Hatchery bridge	189.7	X				
Klamath R. at I-5 Rest Area	176.7	X				
Klamath R. at Walker Bridge Road	159.0	X				

² This site in Iron Gate reservoir is not a routinely-sampled site. During the sampling of September 10, 2008, additional samples were collected at this site to acquire data to help assess the effectiveness of the barrier curtain installed at the log boom.

Samples for phytoplankton speciation, density, and biovolume are preserved in Lugol's solution and sent to Aquatic Analysts in White Salmon, Washington for analysis. The laboratory analysis of phytoplankton speciation and density is done on prepared microscope slides of filtered samples using phase contrast microscopy. Species are counted as algal units of cell, filament, or colony depending on the natural growth form of the species. BGA species are enumerated as individual cells. Algal forms are identified to species or otherwise to the lowest practicable taxonomic level. Biovolumes are estimated by multiplying the cell counts by the average geometric dimensions of the cells for a given phytoplankton taxa.

Samples for determination of microcystin toxin are placed in a cooler on ice and shipped to CH2M HILL Applied Sciences Laboratory in Corvallis, Oregon. The samples are analyzed using the competitive Enzyme-Linked ImmunoSorbent Assay (ELISA) method based on the EnviroLogix QuantiPlate Kit for Microcystins. The quantitation limit is 0.16 µg/L or parts per billion (ppb). This test method does not distinguish between the specific microcystin congeners, but detects their presence to differing degrees. That is, ELISA test results yield one value as the sum of all measurable microcystin variants.

Results of Samples of September 9-11, 2008

Microcystin

Microcystin was above the quantitation limit (i.e., greater than 0.16 µg/L) in 20 of 31 samples obtained during September 9-11, 2008. Of the 20 samples above the quantitation limit, three samples were above the SWRCB (2007) and ODHS (2005) guideline value of 8 µg/L³ for posting advisories in recreation waters. The microcystin concentrations in these three samples were 12.4, 11.1, and 8.9 µg/L taken from Iron Gate reservoir inside the log boom near the forebay (surface grab sample), Copco reservoir at Copco Cove, and Iron Gate reservoir inside the log boom near the forebay (horizontal-integrated sample at 0.5 m depth), respectively.

Two additional samples had a microcystin concentration above the WHO (2003) guideline value of 4 µg/L⁴ for low health risk associated with recreational use of waters. The microcystin concentrations in these two samples were 7.7 and 4.5 µg/L taken from Iron Gate

³ The California State Water Resources Control Board (SWRCB 2007) and Oregon Department of Health Services (ODHS 2005) provide guidelines for posting advisories in recreation waters. These guidelines were developed using information provided in WHO (2003). Both SWRCB (2007) and ODHS (2005) recommend posting advisories in recreation waters under three circumstances: (1) if "scum is present associated with toxigenic species"; (2) if scum is not present, but the density of *Microcystis* or *Planktothrix* is 40,000 cells/ml or greater; and (3) if scum is not present, but the density of all potentially toxigenic BGA is 100,000 cells/ml or greater. Based on WHO (2003) information, SWRCB (2007) and ODHS (2005) indicate that cell counts of 40,000 and 100,000 cells/ml equate to microcystin toxin concentrations of 8 µg/L and 20 µg/L, respectively.

⁴ The World Health Organization (WHO) has recommended guidelines for safe recreational water environments based on a low, moderate, or high probability of adverse health effects from exposure to concentrations of BGA (cyanobacteria) cells and microcystin toxins in recreational waters (WHO 2003). The WHO guideline values for low and moderate probability of adverse health in recreational waters are 20,000 and 100,000 BGA (cyanobacteria) cells/mL, respectively. WHO equates these cell count values to microcystin toxin concentrations of 4 µg/L and 20 µg/L, respectively (WHO 2003). The WHO guideline for high probability of adverse health effects is a narrative; i.e., "Cyanobacterial scum formation in areas where whole-body contact and/or risk of ingestion/aspiration occur". No specific BGA (cyanobacteria) cell or microcystin concentrations are provided by WHO for high probability of adverse health effects. The WHO (2003) guidance values were derived from calculations based on a 20 kg child that would swim for up to two hours (in a day) and would accidentally ingest 0.05 L of water per hour.

reservoir at the log boom in the horizontal-integrated sample and surface grab sample, respectively. Microcystin concentrations were less than 4 µg/L, and mostly less than 2 µg/L in the other samples obtained during September 9-11.

Phytoplankton Cell Densities

PacifiCorp did not order any expedited processing of phytoplankton samples taken during September 9-11, 2008. Due to the presence of visible algae accumulations on the surface of Iron Gate and Copco reservoirs, the California Regional Water Quality Control Board (North Coast Region) issued an advisory on July 29, 2008 urging caution by recreational users of the reservoirs. Because the advisory had already been issued, expedited processing of samples to assess phytoplankton counts for advisory purposes was not needed. Results are not yet available for BGA speciation and cell count data for non-expedited samples. These results will be reported in future memoranda as the results become available from the analytical laboratory.

References

- Carlson, K. and R. Raymond. 2008a. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: April, May, and June 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), June 30, 2008. Prepared for PacifiCorp, Portland OR.
- Carlson, K. and R. Raymond. 2008b. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: June 30 – July 2, 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), July 14, 2008. Prepared for PacifiCorp, Portland OR.
- Carlson, K. and R. Raymond. 2008c. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: July 15-17, 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), July 28, 2008. Prepared for PacifiCorp, Portland OR.
- Carlson, K. and R. Raymond. 2008d. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: July 29-31, 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), August 12, 2008. Prepared for PacifiCorp, Portland OR.
- Carlson, K. and R. Raymond. 2008e. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: August 11-14, 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), August 27, 2008. Prepared for PacifiCorp, Portland OR.
- Carlson, K. and R. Raymond. 2008f. Blue-Green Algae (Cyanobacteria) and Microcystin Monitoring Results in the Vicinity of the Klamath Hydroelectric Project: August 25 to September 2, 2008. Prepared by Ken Carlson (CH2M HILL) and Richard Raymond (E&S Environmental Chemistry), September 12, 2008. Prepared for PacifiCorp, Portland OR.

- ODHS. 2005. Public Health Advisory Guidance for Toxigenic Cyanobacteria in Recreational Waters. Oregon Department of Human Services, Environmental Toxicology Program.
- PacifiCorp. 2008a. Application for Water Quality Certification Pursuant to Section 401 of the Federal Clean Water Act for the Relicensing of the Klamath Hydroelectric Project (FERC No. 2082) in Klamath County, Oregon. Klamath Hydroelectric Project (FERC Project No. 2082). Prepared for: Oregon Department of Environmental Quality, Portland. Prepared by: PacifiCorp, Portland, Oregon. February 2008.
- PacifiCorp. 2008b. Application for Water Quality Certification Pursuant to Section 401 of the Federal Clean Water Act for the Relicensing of the Klamath Hydroelectric Project (FERC No. 2082) in Siskiyou County, California. Klamath Hydroelectric Project (FERC Project No. 2082). Prepared for: State Water Resources Control Board, Division of Water Quality, Water Quality Certification Unit, Sacramento. Prepared by: PacifiCorp, Portland, Oregon. February 2008.
- PacifiCorp. 2008c. Water Quality Studies for Year 2008 for the Klamath Hydroelectric Project. April 22, 2008. Attachment to a letter from Linda Prendergast (PacifiCorp) to Chris Stine (Oregon Department of Environmental Quality) and Jennifer Watts (California State Water Resources Control Board).
- PacifiCorp. 2008d. 2008 Water Quality Monitoring: Sampling Plan. Klamath Hydroelectric Project (FERC Project No. 2082). Prepared by: PacifiCorp Energy, Portland, Oregon. Version: June 30, 2008.
- SWRCB. 2007. Cyanobacteria in California Recreational Water Bodies: Providing Voluntary Guidance about Harmful Algal Blooms, Their Monitoring, and Public Notification. June 2007. Document provided as part of Blue-green Algae Work Group of State Water Resources Control Board (SWRCB) and Office of Environmental Health and Hazard Assessment (OEHHA).
- World Health Organization (WHO). 2003. Guidelines for safe recreational waters, Volume 1 - Coastal and fresh waters, Chapter 8: Algae and cyanobacteria in fresh water. WHO Publishing, Geneva, pp. 136-158.

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
NT	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R					
NT	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R					
NT	Upper Klamath Lake at Wocus Bay	UKL	0.3	R					
NT	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R					
24-May-08	Link River below Upper Klamath Lake	253.1	0.5	R	<0.16	NA	NA	NA	NA
24-May-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
24-May-08	Klamath R. below J.C. Boyle powerhouse	220.0	0.5	R	<0.16	NA	NA	NA	NA
23-May-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	<0.16	NA	NA	NA	NA
NT	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT					
22-May-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	<0.16	NA	NA	NA	NA
NT	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R					
NT	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT					
22-May-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir lower end at log boom	198.6	0.3	R	<0.16	NA	NA	NA	NA
22-May-08	Copco reservoir lower end at log boom	198.6	8.0	INT	<0.16	NA	NA	NA	NA
23-May-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	<0.16	NA	NA	NA	NA
23-May-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	<0.16	NA	NA	NA	NA
23-May-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	<0.16	NA	NA	NA	NA
23-May-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	<0.16	NA	NA	NA	NA
24-May-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	<0.16	NA	NA	NA	NA
23-May-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	<0.16	NA	NA	NA	NA
22-May-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	<0.16	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
NT	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R					
NT	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R					
NT	Upper Klamath Lake at Wocus Bay	UKL	0.3	R					
NT	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R					
3-Jun-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.18	NA	NA	NA	NA
3-Jun-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
5-Jun-08	Klamath R. above Copco reservoir	206.4	0.5	R	0.17	NA	NA	NA	NA
NT	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R					
NT	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT					
NT	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R					
NT	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT					
NT	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R					
NT	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT					
4-Jun-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	0.19	NA	NA	NA	NA
4-Jun-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	0.19	NA	NA	NA	NA
4-Jun-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	0.26	NA	NA	NA	NA
4-Jun-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	0.19	NA	NA	NA	NA
4-Jun-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	0.20	NA	NA	NA	NA
4-Jun-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	<0.16	NA	NA	NA	NA
4-Jun-08	Copco reservoir lower end at log boom	198.6	0.3	R	0.19	NA	NA	NA	NA
4-Jun-08	Copco reservoir lower end at log boom	198.6	8.0	INT	0.19	NA	NA	NA	NA
3-Jun-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	0.20	NA	NA	NA	NA
3-Jun-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	0.23	NA	NA	NA	NA
4-Jun-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	0.18	NA	NA	NA	NA
4-Jun-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	<0.16	NA	NA	NA	NA
5-Jun-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	0.19	NA	NA	NA	NA
5-Jun-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	0.21	NA	NA	NA	NA
3-Jun-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	0.17	NA	NA	NA	NA
3-Jun-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	<0.16	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
19-Jun-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	0.42	NA	NA	NA	NA
19-Jun-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	0.34	NA	NA	NA	NA
19-Jun-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	0.22	NA	NA	NA	NA
NT	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R					
19-Jun-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.65	NA	NA	NA	NA
NT	Klamath R. below Keno dam	233.4	0.5	R					
17-Jun-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	<0.16	NA	NA	NA	NA
18-Jun-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	0.45	0	0	0	0
24-Jun-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	<0.16	NA	NA	NA	NA
24-Jun-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	<0.16	NA	NA	NA	NA
18-Jun-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	0.46	0	0	0	0
18-Jun-08	Copco reservoir lower end at log boom	198.6	0.3	R	<0.16	0	0	0	0
18-Jun-08	Copco reservoir lower end at log boom	198.6	8.0	INT	<0.16	NA	NA	NA	NA
18-Jun-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	0.42	0	0	0	271
18-Jun-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	0.32	0	0	0	0
18-Jun-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	<0.16	NA	NA	NA	NA
18-Jun-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	<0.16	NA	NA	NA	NA
18-Jun-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	<0.16	NA	NA	NA	NA
17-Jun-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	<0.16	0	0	0	0
17-Jun-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	<0.16	0	0	0	0
17-Jun-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	<0.16	0	0	0	0

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
2-Jul-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	0.20	NA	NA	NA	NA
2-Jul-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
2-Jul-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	1.30	NA	NA	NA	NA
2-Jul-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
2-Jul-08	Link River below Upper Klamath Lake	253.1	0.5	R	<0.16	NA	NA	NA	NA
2-Jul-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
30-Jun-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
9-Jul-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	0.22	NA	NA	NA	NA
9-Jul-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	0.20	NA	NA	NA	NA
9-Jul-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	0.25	NA	NA	NA	NA
9-Jul-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	0.21	NA	NA	NA	NA
9-Jul-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	0.21	NA	NA	NA	NA
9-Jul-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	0.23	NA	NA	NA	NA
30-Jun-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	<0.16	0	0	0	2,064
9-Jul-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	0.23	NA	NA	NA	NA
9-Jul-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	0.22	NA	NA	NA	NA
9-Jul-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	0.31	NA	NA	NA	NA
9-Jul-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	0.24	NA	NA	NA	NA
30-Jun-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	0.46	861	964	0	516
1-Jul-08	Copco reservoir lower end at log boom	198.6	0.3	R	<0.16	0	0	0	1,293
1-Jul-08	Copco reservoir lower end at log boom	198.6	8.0	INT	<0.16	NA	NA	NA	NA
30-Jun-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	<0.16	0	0	0	0
30-Jun-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	<0.16	0	0	0	0
1-Jul-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	<0.16	0	1,513	0	0
1-Jul-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	<0.16	NA	NA	NA	NA
30-Jun-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	<0.16	0	0	0	605
30-Jun-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	<0.16	0	0	0	0
30-Jun-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	<0.16	NA	NA	NA	NA
30-Jun-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	<0.16	0	0	0	0

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
15-Jul-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	1.57	NA	NA	NA	NA
15-Jul-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
15-Jul-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	1.31	NA	NA	NA	NA
15-Jul-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
15-Jul-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.33	NA	NA	NA	NA
15-Jul-08	Klamath R. below Keno dam	233.4	0.5	R	0.40	NA	NA	NA	NA
15-Jul-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	0	0	0	391
22-Jul-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	0.31	NA	NA	NA	NA
22-Jul-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
22-Jul-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	0.83	NA	NA	NA	NA
22-Jul-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	0.51	NA	NA	NA	NA
22-Jul-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	0.62	NA	NA	NA	NA
22-Jul-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	0.38	NA	NA	NA	NA
17-Jul-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	0.20	3,191	0	0	0
22-Jul-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	2.00	NA	NA	NA	NA
22-Jul-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	0.28	NA	NA	NA	NA
22-Jul-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	0.66	NA	NA	NA	NA
22-Jul-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	1.11	NA	NA	NA	NA
17-Jul-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	0.45	3,806	0	0	3,654
16-Jul-08	Copco reservoir lower end at log boom	198.6	0.3	R	0.41	0	0	0	1,611
16-Jul-08	Copco reservoir lower end at log boom	198.6	8.0	INT	0.19	NA	NA	NA	NA
17-Jul-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	1.11	0	0	0	0
17-Jul-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	0.73	8,607	0	0	0
16-Jul-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	0.92	11,664	0	0	369
16-Jul-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	NA	NA	NA	NA	NA
17-Jul-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	<0.16	NA	NA	NA	NA
17-Jul-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	0.26	0	0	0	0
17-Jul-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	0.18	861	0	0	0
17-Jul-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	<0.16	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
29-Jul-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	0.25	NA	NA	NA	NA
29-Jul-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
29-Jul-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	0.50	NA	NA	NA	NA
29-Jul-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
28-Jul-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.55	NA	NA	NA	NA
29-Jul-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
30-Jul-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
5-Aug-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	0.21	NA	NA	NA	NA
5-Aug-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
5-Aug-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	21.00	NA	NA	NA	NA
5-Aug-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	8.00	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	21.00	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	4.10	NA	NA	NA	NA
30-Jul-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	4.20	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	13.00	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	2.40	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	3.20	NA	NA	NA	NA
5-Aug-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	2.90	NA	NA	NA	NA
30-Jul-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	3.50	NA	NA	NA	NA
30-Jul-08	Copco reservoir lower end at log boom	198.6	0.3	R	9.40	NA	NA	NA	NA
30-Jul-08	Copco reservoir lower end at log boom	198.6	0.5	R	5.30	NA	NA	NA	NA
30-Jul-08	Copco reservoir lower end at log boom	198.6	8.0	INT	1.90	NA	NA	NA	NA
30-Jul-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	22.00	NA	NA	NA	NA
30-Jul-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	17.00	NA	NA	NA	NA
30-Jul-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	13.00	NA	NA	NA	NA
30-Jul-08	Iron Gate reservoir lower end above log boom	190.2	0.5	R	57.00	NA	NA	NA	NA
30-Jul-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	1.50	NA	NA	NA	NA
30-Jul-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	1.40	NA	NA	NA	NA
30-Jul-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	1.40	NA	NA	NA	NA
31-Jul-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	1.60	NA	NA	NA	NA
31-Jul-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	1.30	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
12-Aug-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	0.56	NA	NA	NA	NA
12-Aug-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
12-Aug-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	1.47	NA	NA	NA	NA
12-Aug-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
11-Aug-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.72	NA	NA	NA	NA
12-Aug-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
12-Aug-08	Klamath R. below J.C. Boyle powerhouse	220.0	0.5	R	<0.16	NA	NA	NA	NA
13-Aug-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
20-Aug-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	0.29	NA	NA	NA	NA
20-Aug-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
20-Aug-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	19.80	NA	NA	NA	NA
20-Aug-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	20.40	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	11.50	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	9.46	NA	NA	NA	NA
13-Aug-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	58.00	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	1.94	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	2.24	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	2.01	NA	NA	NA	NA
20-Aug-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	1.26	NA	NA	NA	NA
13-Aug-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	48.00	NA	NA	NA	NA
13-Aug-08	Copco reservoir lower end at log boom	198.6	0.3	R	20.00	NA	NA	NA	NA
13-Aug-08	Copco reservoir lower end at log boom	198.6	0.5	R	15.00	75,726	7,080	0	19,264
13-Aug-08	Copco reservoir lower end at log boom	198.6	8.0	INT	2.50	NA	NA	NA	NA
13-Aug-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	11.00	NA	NA	NA	NA
13-Aug-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	3.50	NA	NA	NA	NA
13-Aug-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	4.90	NA	NA	NA	NA
13-Aug-08	Iron Gate reservoir lower end above log boom	190.2	0.5	R	2.30	10,197	245	0	6,544
13-Aug-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	2.40	NA	NA	NA	NA
13-Aug-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	3.30	NA	NA	NA	NA
13-Aug-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	1.60	NA	NA	NA	NA
14-Aug-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	2.50	NA	NA	NA	NA
14-Aug-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	1.90	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
26-Aug-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	3.26	NA	NA	NA	NA
26-Aug-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
26-Aug-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	1.73	NA	NA	NA	NA
26-Aug-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
25-Aug-08	Link River below Upper Klamath Lake	253.1	0.5	R	0.65	NA	NA	NA	NA
26-Aug-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
26-Aug-08	Klamath R. below J.C. Boyle powerhouse	220.0	0.5	R	<0.16	NA	NA	NA	NA
27-Aug-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
2-Sep-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	0.40	NA	NA	NA	NA
2-Sep-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	<0.16	NA	NA	NA	NA
2-Sep-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	20.10	NA	NA	NA	NA
2-Sep-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	6.12	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	7.21	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	4.81	NA	NA	NA	NA
27-Aug-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	22.80	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	4.20	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	2.35	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	1.23	NA	NA	NA	NA
2-Sep-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	1.06	NA	NA	NA	NA
27-Aug-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	95.30	NA	NA	NA	NA
27-Aug-08	Copco reservoir lower end at log boom	198.6	0.3	R	19.50	NA	NA	NA	NA
27-Aug-08	Copco reservoir lower end at log boom	198.6	0.5	R	23.10	64,199	0	0	48,149
27-Aug-08	Copco reservoir lower end at log boom	198.6	8.0	INT	2.38	NA	NA	NA	NA
27-Aug-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	4.19	NA	NA	NA	NA
27-Aug-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	9.28	NA	NA	NA	NA
27-Aug-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	5.39	NA	NA	NA	NA
27-Aug-08	Iron Gate reservoir lower end above log boom	190.2	0.5	R	22.20	47,492	0	0	21,911
27-Aug-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	1.20	NA	NA	NA	NA
27-Aug-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	1.57	NA	NA	NA	NA
28-Aug-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	4.90	NA	NA	NA	NA
28-Aug-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	6.19	NA	NA	NA	NA
28-Aug-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	0.43	NA	NA	NA	NA

Table 2. Blue-green algae cell count (cells/mL) and microcystin concentration (ug/L) in sites sampled to date during 2008 by PacifiCorp in Iron Gate, Copco, and J.C. Boyle reservoirs and other sites in the Klamath River.

Codes:

- R Regular grab sample (at surface)
- INT Integrated grab sample (from surface to 8 m)
- NA Results not available to date
- NT Sample not taken

Date	Location	River Mile	Depth (m)	Sample Type	Microcystin (ug/L)	<i>Microcystis</i> (cells/mL)	<i>Anabaena</i> (cells/mL)	<i>Planktothrix</i> (cells/mL)	<i>Aphanizomenon</i> (cells/mL)
9-Sep-08	Upper Klamath Lake near Eagle Ridge ramp	UKL	0.3	R	1.75	NA	NA	NA	NA
9-Sep-08	Upper Klamath Lake near Hagelstein Park	UKL	0.3	R	<0.16	NA	NA	NA	NA
9-Sep-08	Upper Klamath Lake at Wocus Bay	UKL	0.3	R	2.11	NA	NA	NA	NA
9-Sep-08	Upper Klamath Lake at Pelican Bay ramp	UKL	0.3	R	<0.16	NA	NA	NA	NA
9-Sep-08	Link River below Upper Klamath Lake	253.1	0.5	R	1.48	NA	NA	NA	NA
9-Sep-08	Klamath R. below Keno dam	233.4	0.5	R	<0.16	NA	NA	NA	NA
9-Sep-08	Klamath R. below J.C. Boyle powerhouse	220.0	0.5	R	<0.16	NA	NA	NA	NA
10-Sep-08	Klamath R. above Copco reservoir	206.4	0.5	R	<0.16	NA	NA	NA	NA
16-Sep-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	0.5	R	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir upper end at Copco Village (SB 1)	204.0	5.0	INT	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	0.5	R	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir upper end near "narrows" (SB 2)	203.0	6.0	INT	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	0.5	R	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle above Mallard Cove (SB 3)	202.0	8.0	INT	NA	NA	NA	NA	NA
10-Sep-08	Copco reservoir at Mallard Cove ramp	201.5	0.3	R	0.76	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	0.5	R	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle below Mallard Cove (SB 4)	201.0	8.0	INT	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	0.5	R	NA	NA	NA	NA	NA
16-Sep-08	Copco reservoir middle near Copco Cove (SB 5)	200.0	8.0	INT	NA	NA	NA	NA	NA
10-Sep-08	Copco reservoir at Copco Cove ramp	200.0	0.3	R	11.10	NA	NA	NA	NA
10-Sep-08	Copco reservoir lower end at log boom	198.6	0.3	R	1.66	NA	NA	NA	NA
10-Sep-08	Copco reservoir lower end at log boom	198.6	0.5	R	2.32	NA	NA	NA	NA
10-Sep-08	Copco reservoir lower end at log boom	198.6	8.0	INT	2.38	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir at Camp Creek area	192.8	0.3	R	2.12	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir at Williams boat ramp	192.4	0.3	R	0.29	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	0.3	R	4.46	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	0.5	R	7.73	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	8.0	INT	2.07	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	10.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	20.0	R	0.21	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	30.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir lower end above log boom	190.2	40.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir forebay	190.1	0.3	R	12.40	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir forebay	190.1	0.5	R	8.88	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir forebay	190.1	10.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir forebay	190.1	20.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate reservoir forebay	190.1	30.0	R	<0.16	NA	NA	NA	NA
10-Sep-08	Iron Gate powerhouse tailwaters	190.1	0.5	R	1.86	NA	NA	NA	NA
10-Sep-08	Klamath R. at Iron Gate Hatchery bridge	189.7	0.5	R	2.05	NA	NA	NA	NA
11-Sep-08	Klamath R. at I-5 Rest Area	176.7	0.5	R	2.46	NA	NA	NA	NA
11-Sep-08	Klamath R. at Walker Bridge Road	159.0	0.5	R	2.49	NA	NA	NA	NA